

	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.
<i>Bridges—continued.</i>												
Brought forward ...												
Three Occupation Bridges over Railway at 4-76, 5-77, and 10-21:—												
Quantities same as District Road Bridge, 3 at £120 2s.				360	6	0						
Bridge under District Road, near 1-50:—												
Allow for Removal and Re-erection ...	20	0	0									
Extra Timber, 40 c. ft. at 3s....	6	0	0									
				26	0	0						
Culverts and Drains:—												
1 Culvert, including Excavation, 34 l. yds. at 180s. ...	306	0	0									
5 Culverts, including Excavation, 95 l. yds. at 140s. ...	665	0	0									
6 Culverts, including Excavation, 53 l. yds. at 45s. ...	119	5	0									
1 Culvert under Road, including Excavation, 25 l. yds. at 46s. 2½d. ...	57	15	2½									
1 Culvert with Gate, including Excavation, 11 l. yds. at 47s. 8½d. ...	26	5	0½									
1 Culvert with Gate, including Excavation, 10 l. yds. at 48s. ...	24	0	0									
2 Culverts, including Excavation, 20 l. yds. at 10s. ...	10	0	0									
12-inch Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 12s. ...	90	0	0									
9-inch Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 9s. ...	67	10	0									
6-inch Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 6s. ...	45	0	0									
				1,410	15	2½						
Inspector's Cottage, complete, as specified ...				115	0	0						
				£12,935	4	1½						
COMPLETION OF CLUTHA CONTRACT.												
<i>Tender of Blair and Watson, £13,478 3s. 10d.</i>												
Fencing:—	£	s.	d.	£	s.	d.						
Turf Fencing, 930 chs. at 14s 6d. ...	674	5	0									
Post, Rail, and Wire Fencing, 640 chs. at 20s. ...	640	0	0									
				1,314	5	0						
Clearing Line, 855 chs. at 4s....				171	0	0						
Cuttings:—												
173,630 c. yds. at 1s. 3d. ...	10,851	17	6									
6,660 c. yds. at 1s. 9d. ...	582	15	0									
				11,434	12	6						
Embankments, 153,500 c. yds.												
Soiling Slopes of Embankments, 16,000 sup. yds. ...				141	13	4						
Pitching Slopes, 1,320 s. yds. at 4s. 6d. ...				297	0	0						
Formation, including side ditches, 855 chs. at 10s. ...				427	10	0						
Ditches:—												
Ditches shown on Drawings, 60 chs. at 12s. ...												
Ditches at undefined places, 100 chains at 12s. ...				96	0	0						
Level Crossings:—												
Gates and Wickets complete, 4 pairs at £7 10s. ...	30	0	0									
Ordinary Crossings complete, 10 pairs at £15 ...	150	0	0									
				180	0	0						
Road Alterations.												
District Road:—												
Earthwork, including formation, 900 c. yds. at 1s. 3d....				56	5	0						
Main South Road:—												
Earthwork, including formation, 220 c. yds. at 1s. 3d. ...	13	15	0									
Pitching and Metalling, 40 l. yds. at 5s. ...	10	0	0									
				23	15	0						
Carried forward ...												
<i>Brought forward ...</i>												
District Roads:—												
Earthwork, including formation, 1,200 c. yds. at 1s. 2d. ...							70	0	0			
Where directed—Earthwork, including formation, 2,000 c. yds. at 1s. 2d. ...	116	13	4									
Metalling, 500 c. yds. at 7s. ...	175	0	0									
							291	13	4			
Bridges.												
Bridge over Lovel's Creek:—												
Piles, including Hooping, Driv- ing, &c., 144 l. ft. at 3s. 4d. ...	24	0	0									
Timber in Walings and Braces, 91 c. ft. at 3s. 4d. ...	15	3	4									
Timber Beams, 120 c. ft. at 3s. 4d. ...	20	0	0									
							59	3	6			
Iron in Pile Shoes, 120 lbs. at 4½d. ...	2	5	0									
Iron Straps, Bolts, and Spikes, 300 lbs. at 4½d. ...	5	12	6									
							7	17	6			
Bridge over Stoney Creek:—												
Piles, including Hooping, Driv- ing, &c., 144 l. ft. at 3s. 4d. ...	24	0	0									
Timber in Walings and Braces, 91 c. ft. at 3s. 4d. ...	15	3	4									
Timber Beams, 120 c. ft. at 3s. 4d. ...	20	0	0									
Iron in Pile Shoes, 120 lbs. at 4½d. ...	2	5	0									
Iron Straps, Bolts, and Spikes, 300 lbs. at 4½d. ...	5	12	6									
							67	0	10			
District Road Bridge over Rail- way, at 7-75:—												
Excavation for Cills and Re- filling Trenches, 18 c. yds. at 1s. 6d. ...	1	7	0									
Timber in Cills and Plates, 68½ ft. at 3s. 4d. ...	11	8	4									
Timber Uprights and Bracings, 152½ c. ft. at 3s. 4d. ...	25	8	4									
Timber Beams and Struts, 163 c. ft. at 3s. 4d. ...	27	3	4									
Timber Planking, including Spikes, 190 c. ft. at 3s. 4d. ...	31	13	4									
Timber Parapets and Ballast Beams, 76 c. ft. at 3s. 4d....	12	13	4									
Iron in Straps and Bolts, 280 lbs. at 4½d. ...	5	5	0									
							114	18	8			
Three Occupation Bridges over Railway, at 4-76, 5-77, and 10-24:—												
Quantities same as District Road Bridge, 3 at £114 18s. 8d. ...							344	16	0			
Bridge under District Road:—												
Extra Timber, 40 c. ft. at 3s. 4d. ...							6	13	4			
Culverts and Drains:—												
1 Culvert, including Excava- tion, 34 l. yds. at £10 12s. ...	360	8	0									
5 Culverts, including Excava- tion, 95 l. yds. at £6 14s. ...	636	0	0									
9 Culverts, including Excava- tion, 99 l. yds. at £2 8s. ...	247	12	0									
2 Culverts, including Excava- tion, 20 l. yds. at £2 10s ...	50	0	0									
12-in. Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 11s. ...	82	10	0									
9-in. Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 8s. ...	60	0	0									
6-in. Glazed Earthenware Pipes, including Excavation, 150 l. yds. at 5s. ...	37	10	0									
							1,464	0	0			
Inspector's Cottage, complete, as specified ...							110	0	0			
Deduct for Work done, use of Tools, &c. ...							3,200	0	0			
							£13,478	3	10			