Bridges.	£
Clyde Bridge	8,000
Bannockburn Bridge	2,000
Tinkers	100
Thompson's footbridge	25
Nevis	70
Fraser's	45
Rocky Point Bridge, approaches	200
Cromwell Bridge, abutments	250
Total damage to bridges	£10,690

Punts.	£
Alexandra punt	150
Bendigo "	150
Alberton "	150
Total damage to punts	£450

Miscellaneous.	£
Removing and re-erecting Clyde Hospital	300
Total damage to public works in Vincent County	£19,990

The damage to roads consists chiefly in slips that have buried or carried away the roads in the steep sidlings along which they are made.

The smaller bridges have been almost entirely carried away, but the abutments of the Clyde Bridge remain. The original structure of the Cromwell Bridge is uninjured, the damage done being to the anchorage for the suspension ropes built a few years ago. The river at the Rocky Point Bridge seems to have a tendency to make a new channel for itself clear of the bridge. If this takes place it will entail an extra expenditure of £2,000 or £3,000 in lengthening the bridge or constructing protective works.

Lake County.

An approximate estimate of the damage done to public works in the Lake County is as follows:—

Roads and Tracks, including Bridges.	£
Kirtleburn to Morven Ferry	7,000
Morven Ferry to Arrowtown, with bridge over Arrow River	1,570
Arrow to Lower Shotover, with bridge	2,000
Shotover Hill Road	500
Frankton to Queenstown	600
Queenstown to Arrow *viâ* Arthur's Point	1,450
Queenstown to Shotover Bridge	3,500
Queenstown to Moke Creek and Moonlight	800
Queenstown to Head of Lake	500
Frankton to Kingston	550
Road to Arrowtown Reefs	3,000
Arrow Valley tracks	400
Arrow to Cardrona and Pembroke	950
Pembroke to head of Lake Wanaka	550
Arrow to Matatapu	100
Greenstone to Kinlock	70
Greenstone to Hollyford	500
Hollyford to Jamestown	900
Kingston to Athol	500
Dart Valley Road and Tracks	500
Streets in Queenstown	1,000
Total damage to public works in Lake County	26,940

The damage above estimated consists chiefly of slips in sidling ground, as in Vincent County, the most serious one being at the Nevis Bluff, where an immense quantity of rock has come down. This will completely close up the road between Queenstown and Cromwell for dray-traffic for a long time. At present it is scarcely passable for foot passengers.

Summary and Recommendations.

The following is an abstract of damage done to public works in the various counties:—

	£	£
Bruce—Roads	2,250	
Bridges	6,100	
Various	400	
Total in Bruce County		8,750