

AUCKLAND AND MERCER—continued.

Description.	Unit.	Quantity.	Rate.	Amount.	Total.
				£ s. d.	£ s. d.
Permanent-way, New Zealand ...	...	...	...	36,732 17 4	
Contingencies ...	...	...	...	4,594 2 8	
					41,337 0 0
Profit ...	...	...	...	3,673 0 0	
Management ...	...	...	...	3,673 0 0	
Maintenance ...	...	...	...	860 0 0	
					8,206 0 0
					49,543 0 0
Rolling-stock, New Zealand ...	...	...	...	2,379 10 0	
Contingencies ...	...	...	...	297 10 0	
					2,677 0 0
Profit ...	...	...	...	237 0 0	
Management ...	...	...	...	237 0 0	
Maintenance ...	...	...	...	179 0 0	
					653 0 0
					3,320 0 0
Grand total ...	...	...	...	...	£168,924 0 0

MEMO.—The portions of these schedules printed in smaller type are entered in the "Contractor's Price Book" in lead pencil only.

NAPIER AND PAKIPAKI (16 miles 3 chains, and 1 mile of sidings).—J. BROGDEN AND SONS.

Description.	Unit.	Quantity.	Rate.	Amount.	Total.
				£ s. d.	£ s. d.
<i>Fencing.</i>					
Single fencing ...	ch.	320	30/	480 0 0	
Gates ...	pair	10	£11	110 0 0	
Cattle-stops ...	...	25	£16	400 0 0	
Contingencies, 12½ per cent. ...	...	...	...	124 0 0	
					1,114 0 0
<i>Grading.</i>					
Excavation—					
Formation ...	c. yd.	67,566	1/	3,378 6 0	
Ditch in cuts ...	ch.	23	15/	17 5 0	
Forming line ...	"	306	£1	306 0 0	
Trimming, 16m. 3ch. ...	"	1,283	10/	641 10 0	
Contingencies, 12½ per cent. ...	...	...	...	542 19 0	
Road diversions ...	ch.	55½	£4	222 0 0	
Level crossings, 1st class ...	...	4	£82	328 0 0	
" 2nd class ...	...	3	39/10/	118 10 0	
" 3rd class ...	...	3	38/6/	114 18 0	
Contingencies, 12½ per cent. ...	...	...	...	97 12 0	
					5,767 0 0
<i>Bridges and Culverts.</i>					
Timber ...	C b. m.	1,906½	£2	3,812 10 0	
Piles ...	ft.	6,711	4/6	1,509 19 6	
Iron ...	lb.	37,254	/6	931 7 0	
Excavation in foundations ...	c. yd.	860	1/6	64 10 0	
Outfalls, not to exceed ...	"	5,000	1/6	375 0 0	
Contingencies, 12½ per cent. ...	...	...	...	836 13 6	
					7,530 0 0
<i>Permanent-way in New Zealand.</i>					
Ballast ...	c. yd.	1,467	2/	146 14 0	
Sleepers ...	...	2,050	3/	307 10 0	
Laying ...	l. yd.	1,760	2/	176 0 0	
Cartage ...	...	132	5/6	36 6 0	
Waste and loss ...	...	...	...	20 0 0	
Freight, &c., from Auckland to Napier ...	...	...	...	686 10 0	
Contingencies, 12½ per cent. ...	...	...	...	102 4 0	
				98 6 0	
For 1 mile ...	...	...	...	887 0 0	
	m. ch.	16 3	£887	...	14,225 0 0
Carried forward ...	...	...	...	...	28,636 0 0