

213 miles from Auckland and Wellington, and 2,600 it, above sea-level. Five 100 it, spans, ten 36 it, plate girder spans on six concrete piers and abutments, and on five steel braced piers resting on concrete base blocks; length over all, 860 ft.; height over all, 260 ft.; grade, level; excavations, 7,720 cubic yards; concrete, 6,060 cubic yards; steel, 952 tons. Cost. £356.832.